BoQ FOR PROPOSED TRUCK LOADING/WAGON OFF-LOADING YARD AT KAJIADO

		RFQ			
ITEM	**DESCRIPTION OF WORKS**	**UNIT**	**QTY**	**RATE**	**AMOUNT**
	ELEMENT 1 : PRELIMINARY				
	GENERAL PRELIMINARY				
1.01	Allow contractual requirements, training levy with holding tax and other GoK statutes necessary to commence and proceed with the works to completion.	SUM	1		
1.02	Allow preliminaries to cover overheads, transport, security, storage, water for construction, power supply, clients safety requirements, "Contractors all Risks" and other insurances as required by the general conditions of Contract, all temporary works not covered elsewhere under specific items of the bills of Quantities (Provisional Sum not to exceed 10% of Contract Sum)	SUM	1		
	TOTAL FOR PRELIMINARY CARRIED TO GRAND SUMMARY				

ITEM	DESCRIPTION OF WORKS	UNIT	QTY	RATE	AMOUNT
	ELEMENT 2 : EXCAVATION & FILLING				
	(ALL PROVISIONAL)				
	Excavations				
2.01	Excavate in soft material, the entire yard area	CM	6,156		
	Disposal approx. 2Km				
2.02	Cart away excavated material as directed by the Engineer.	CM	6,156		
	Filling				
2.03	Supply and lay selected sub grade material in layers not exceeding 200mm; any layer consisting of rock, to be moistened to a uniform moisture content within ± 2% of optimum moisture content and thoroughly compacted to 95% of the maximum density as determined by AASHTO - T99. (Boulders as sub-grade to be approved by Eng.)	CM	4,110		
2.04	Supply and lay approved topping material on sub-base in 150mm thick layers; material to be moistened to a uniform moisture content within ±2% of optimum moisture content and thoroughly compacted to 100% of the maximum density as determined by AASHTO - T99.	CM	2,055		
	TOTAL FOR ELEMENT 2 CARRIED TO GRAND SUMMARY				

ITEM	DESCRIPTION OF WORKS	UNIT	QTY	RATE	AMOUNT

GRAND SUMMARY

No.	Element	Page No	Amount (Kshs.)
A	Element 1 :General Preliminaries, PC and Provisional Sum	1	
B	Element 2 : Excavation & Filling	2	
J	**Total**		**-**
K	ADD 10% Contingency		-
L	**Sub-Total**		**-**
M	Add 16% VAT of {G}		-
N	**GRAND SUMMARY Carried Forward To Tender Document - Kajiado Truck Loading Yard**		**-**